



SERVICES PROVIDED BY GCI

- Owner's Authorized Representative (OAR)
- Project Management
- Inspection

MAIN PROJECT ELEMENTS

- Wind Cones
- Underground Cable, Conduit, Duct Banks
- Electrical Vault Equipment
- Airfield Lighting Systems
- Airfield Guidance Signs
- Runway and Taxiway Marking
- Beacon Tower Painting

ORLANDO EXECUTIVE AIRPORT (OEA) BP-33, Airfield Lighting and Signage Improvements - Phase 2

This construction project replaced airfield signs to support the new Orlando Executive Airport (OEA) taxiway designations in accordance with FAA AC 150/5340-18D.

The project also included replacing portions of the airfield lighting systems, NAVAID homerun conductors, addition of five new wind cones to NAVAIDs, painting of the Beacon Tower, a new regulator in the electrical vault, modification of the Air Traffic Control (ATC) tower lighting panel graphics to reflect new taxiway designations, and removal and replacement of hold-bar markings.



CONSTRUCTION COST: \$1,053,213
COMPLETION DATE: August 2008