



SERVICES PROVIDED BY GCI

- Owner's Authorized Representative (OAR)
- Project Management (PM)
- Inspection (CEI)

MAIN PROJECT ELEMENTS

- Roofing
- Glazing
- Qualitative Testing
- Interior Finishes
- Exterior Sealants

ORLANDO INTERNATIONAL AIRPORT BP-370A, Airside 1&3 Rehabilitation & Hurricane Restoration, Phase I

This project consisted of the design and construction of new roofs at Airsides 1 and 3 of the Orlando International Airport to repair damages caused by the 2004 Hurricanes. The work included replacement of windows in the wings of both airside and completion of the permanent repairs to interior finishes.

Other elements of the project included new roofing with mechanical connections to the roof deck, construction of curbs for future skylights, relocation of roof drains, addition of scuppers, removing 104 existing window systems and replacing them with new laminated-insulated glass curtain wall systems, interior sheetrock repairs, refinishing and painting.

CONSTRUCTION COST: \$12,122,171
COMPLETION DATE: AUGUST 2006

