



SERVICES PROVIDED BY GCI

- Owner's Authorized Representative (OAR)
- Inspection (CEI)

MAIN PROJECT ELEMENTS

- Asphalt Milling
- Base Repair
- Paving
- Striping

ORLANDO INTERNATIONAL AIRPORT BP-344, Loop Road Milling & Resurfacing

This project consisted of the milling, resurfacing, and striping of the Orlando International Airport Loop Road System. The Loop Road System includes the main roadway, auxiliary lanes, and ramps and single width roadways leading to and from arriving and departing flight levels, commercial vehicle areas, parking lot lanes, and rental car businesses.

Over 24 lane miles of roadway were resurfaced, two areas of base failure were repaired, and more than 34 miles of roadway striping was installed including multiple pavement messages and specialty messages.

To minimize impact to the traveling public on a road network experiencing 32,000 Annual Average Daily Traffic (AADT) levels, all work was performed at night with single lane closures occurring between 12:00 A.M. and 3:00 A.M.



CONSTRUCTION COST: \$2,353,747
COMPLETION DATE: NOVEMBER 2003