



#### SERVICES PROVIDED BY GCI

- Owner's Authorized Representative (OAR)
- Project Management (PM)
- Construction Inspection

#### MAIN PROJECT ELEMENTS

- Replacement of AHU's
- Replacement of exterior condensing units
- Installation of new exhaust fans in condenser areas

## — ORLANDO INTERNATIONAL AIRPORT V-718, Airside 4 Delta Communication Room HVAC Replacement

This project replaced two (2) air handling units and condensing units at the Airside 4 Delta communication room at the Orlando International Airport. Airline Operations, Maintenance, Concessions, Security and Life Safety areas of the Airport remained air-conditioned at all times throughout the renovation, maintaining full capabilities with no disruptions.

Included in the scope was the installation of new plenum supply grilles, new refrigerant piping with insulation, new isolator pads for equipment, reclamation of existing freon, the removal and reinstallation of ceiling grid and tiles as required for installation of equipment, and the patching of the openings where existing refrigerant lines were removed. Also included was the installation of two (2) new exhaust fans with ductwork, wall shutters, and required starters and disconnects for the new condensing units.

**CONSTRUCTION COST: \$190,000**  
**COMPLETION DATE: August 2014**

